MYSORE SPECIAL DIVISION.

Notice dated 3rd October 1930.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Special Division, Mysore, up to Monday the 27th October 1930, till 2 P.M., for Extending Vice-Chancellor's Quarters at Mysore. An abstract of approximate quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred (Rs. 300) in cash as earnest money, and be superscribed "Tender for Extending Vice-Chancellor's Quarters at Mysore," in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest tender or any tender or assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which the tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimate rates" will be accepted.

10. Once the tender has been accepted no claim for any concession or higher rates will be entertained.

11. The work to be executed as per Public Works Department Specifications.

12. The decision of the Chief Engineer in all matters *re* measurements, rates, etc., shall be final and legally binding.

Approximate quantities required for Extending the Vice-Chancellor's Quarters at Mysore

Items of work	Unit	Quantity	Rate in figures	Rate in words
1. Earthwork excavating foundation in ordinary or gravelly soil and filling in basement with consolidation.	C.yds.	76	Rs. a. p.	
2. Stone jelly concrete in chunam mortar ...	C.ft.	598		
3. Burnt brick in mortar for filling foundation and basement.	"	1,898		
4. Burnt brick in mortar for superstructure about 14 ft. high.	"	2,538		
5. Table moulded bricks in chunam mortar mixed with cement 1 cement to 10 mortar for pillars with reinforced concrete bond slabs or burnt stone slabs 6" thick and for the full area at every 4 feet.	"	304		
6. Burnt stone slabs 6" thick one line dressed including fixing in mortar as lintles, etc.	S.ft.	111		
7. Relieving arches with burnt brick in chunam mortar 1½' thick.	C.ft.	110		
8. Rolled steel British Standard joists including hoisting, fixing and painting 2 coats of silicate over one coat of varnish for the visible portions and one coat of anti corrosive paint for the portions imbedded in walls.	Cwt.	81½		
9. Angle iron including fixing in walls with bores and anti corrosive paint.	lbs.	457		

Items of work	Unit	Quantity	Rate in figures	Rate in words
			Rs. a. p.	
10. Extra iron work for tie rod, bolts, nuts, etc., with anti corrosive paint.	lbs.	400		
11. Teakwood doors of 4′×8½′ half panelled half glazed with brass fittings as per marriyots specifications with iron clamps and two coats of silicate painting, etc., complete.	S.ft.	68		
12. Teakwood French windows fully glazed with brass fittings iron clamps, etc., complete, as per design for sizes 4′x7′, 3½′x6′ and 2½′ x 6′ with two coats silicate painting	,,	193		
13. Jack arch terrace roofing including Kappe in chunam with two courses of flat tiles and chunam plastering, etc., complete, mean actual area to be measured.	Sqr'	12·27		
14. Flooring with Mangalore or Yelahanka square tiles on 3″ concrete bed and cement pointing.	,,	12·70		
15. Plastering with chunam mortar ¾″ thick to walls	,,	59·00		
16. Cornice 9″ thick with burnt brick in mortar including plastering and masonry up to 6″ thickness in wall.	R.ft.	·131		
17. Cuddapah slab wall plates under joists set in chunam mortar.	S.ft.	215		
18. Fixing burnt stone slabbed bond stones in chunam mortar 2½′x1½′ and 6′ thick to join old and new walls.	Each	20		
19. Calcarium wash to interior walls 2 coats ...	Sqr.	19·60		
20. White washing two coats	,,	71·83		
21. Boxing girders to sizes with cement concrete and cement plastering ½″ thick, etc., complete.	R.ft.	104		
22. Burnt stone slabs 2 line dressed and fixed in chunam mortar.	S.ft.	24		
23. Forming base capitals to pillars with brick in chunam mortar including plastering.	Each	9		
24. Clearing site earthwork in ordinary or gravelly soil.	C.yds.	...		
25. Parapet wall 2½′ high and 4½′ thick with burnt brick in mortar with balastrades including plastering.	R.ft.	217		

Abstract Notice

The attention of the public is invited to the notice, dated 8th September 1930, calling for tenders for constructing the front main building of the Defectives Institute at Mysore, published on pages 1171 to 1174, Part VI of the *Mysore Gazette*, dated 25th September 1930.

The last date for receipt of tender is 20th October 1930.

V. V. PATANKAR,
Executive Engineer.

MYSORE RAILWAYS.

Abstract Notification dated 25th September 1930.

The attention of the public is invited to the Notification published in pages 1176 and 1177 of Part VI of the *Mysore Gazette*, dated 25th September 1930, calling for tenders for Widening cuttings and banks on Bangalore-Mysore-Nanjangud Section. The last date for receiving the tenders is 25th October 1930 till 2 P.M.

Y K. RAMACHANDRA RAU,
Executive Engineer.

Abstract Notification dated 10th October 1930.

The attention of the public is invited to the Notification published in pages 1226 and 1227 of Part VI of the *Mysore Gazette*, dated 9th October 1930, calling for tenders for the construction of 1-12 feet Girder Bridge across the Railway line for the Irwin Canal, Maddur Branch at mile 260—3-4. The last date for receiving the tenders is 18th October 1930, till 2 P.M.

V. RAMANUJALU NAIDU,
Executive Engineer.